

CITY OF GOODYEAR
DEVELOPMENT SERVICES DEPARTMENT
Approved Asphaltic Concrete Mix Designs



Supplier	Hot Plant #	Hot Plant Location	Product Code	Mix Size	Mix Type	Supplier Designation	Max Unit Wt. (Rice)	Percent Oil	Oil Supplier	Stamp Date	Exp. Date
Vulcan	5180	Sun City	271515S	3/4"	Gyratory	MAG Gyratory	150.5	4.6	Wright	4/25/22	4/24/24
Vulcan	5180	Sun City	271517S	3/4"	Gyratory	MAG Gyratory	151.5	4.6	Marathon	1/10/23	1/9/25
Vulcan	5180	Sun City	271518S	3/4"	Marshall	MAG Marshall	152.9	5.0	Western	1/10/23	1/9/25
Vulcan	5182	43rd Ave	271517D	3/4"	Gyratory	MAG Gyratory	150.6	4.7	Holly Frontier	1/4/23	1/3/25
Vulcan	5223	Gomez	271517G	3/4"	Gyratory	MAG Gyratory	150.8	4.5	Holly Frontier	1/10/23	1/9/25
Vulcan	5184	West Broadway	271517W	3/4"	Gyratory	MAG Gyratory	150.2	4.9	Holly Frontier	1/10/23	1/9/25
Vulcan	5184	West Broadway	271518W	3/4"	Marshall	MAG Marshall	151.0	5.4	Holly Frontier	1/13/23	1/12/25
SW Asphalt	4	El Mirage	421AH	1/2"	Gyratory	MAG/EVAC SHRP	152.6	5.3	Holly Frontier	12/6/23	12/5/25
SW Asphalt	4	El Mirage	431AH	3/4"	Gyratory	MAG/EVAC SHRP	152.4	5.0	Holly Frontier	12/6/21	12/5/23
SW Asphalt	4	El Mirage	431DH	3/4"	Marshall	MAG/EVAC SHRP	152.8	5.0	Holly Frontier	12/6/21	12/5/23
SW Asphalt	10	New River	121AH	1/2"	Gyratory	MAG/EVAC SHRP	146.2	5.3	Holly Frontier	12/6/21	12/5/23
SW Asphalt	10	New River	131AH	3/4"	Gyratory	MAG/EVAC SHRP	147.0	5.0	Holly Frontier	12/6/21	12/5/23
Soltera	2	Ray Rd & Tuthill Rd	S23-2-3-W	3/4"	Marshall	MAG Marshall	153.9	5.1	Western	12/23/22	12/22/24

- 1. Asphalt mix designs that are not listed require submittal for review and approval a minimum of two weeks prior to the installation date.**
- 2. All aggregate material will be tested using the LA Abrasion test method at least 45 days prior to installation of the asphalt mix for any paving project larger than 500 tons. The test results shall be supplied no later than five (5) days prior to the installation date.**
- 3. No changes to the approved mix design may be made without approval by the City Engineer.**